

### Telecoms / Voice and Data

To facilitate this ambition of getting the quality right, these checks should take place:

- Ensure adequate separation from all other cables and heat sources
- Ensure sufficient capacity in containment for future modifications / additions?
- Ensure cables runs do not exceed 90m
- Ensure cable testing result printouts available
- If fire suppression is provided to Comms Rooms the room will need to be airtight and pressure tested and pressure relief valves required
- Ensure building is sufficiently dry, clean and at the correct temperature for installation of data cables
- Protect all cables within floor voids during construction period. (damaged cables cannot be repaired - they must be replaced)
- Check that any air conditioning has been operating for a sufficient proving period prior to commissioning of comms room equipment and systems
- Coordinate water services to avoid running over comms rooms

#### Our Quality vision:

We will get it right first time on all our projects by delivering exceptional customer service

