

As-Built Drawings

To facilitate this ambition of getting the quality right, these checks should take place:

- Ensure these are started early and progressed as the systems are installed to prevent them from being used as an excuse to delay handover
- Chase specialist suppliers to provide these in the form the customer requires (disc / paper / software format)
- Do the as-built drawings need to indicate plant, valve, and fire detection identity tag numbers?
- Update fire plan
- Ensure that the draft O&M manuals are issued three months prior to project completion, and as-built drawings are available in a timely manner

Our Quality vision:

We will get it right first time on all our projects by delivering exceptional customer service

