

# Combined Heat and Power Units

To facilitate this ambition of getting the quality right, these checks should take place:

- Give sufficient notice for the utility companies' G59 inspection process
- Check that the customer has signed up and returned the Independent Generating Agreement before operating the CHP unit
- Has the sizing of the pipework serving the heat dump exchanger been carried out correctly?
- Ensure CHP is commissioned correctly to operate as lead boiler
- Are the louvres of sufficient size to facilitate the heat rejection?

### Our Quality vision:

We will get it right first time on all our projects by delivering exceptional customer service

